



**West Bengal Zoo Authority**  
**Office of the Director**  
**North Bengal Wild Animals Park,**  
5<sup>th</sup> Mile, Sevoke Road, Salugara, Siliguri-734008 (W.B.)  
Email Id: - [dirnbwap@gmail.com](mailto:dirnbwap@gmail.com)

**SUBJECT:- QUOTATION FOR TRUSS OF PORCUPINE ENCLOSURE AT NBWAP.**

NIQ No.- **66** /Q-28(MISC)/NBWAP/2024-25, Dated: - **15 / 07 /2024**

Sealed Quotations are invited from bonafide Contactor/Firms for Truss of Porcupine Enclosure at NBWAP. Quotationers are requested to submit their rate in a sealed cover addressed to the undersigned by the Director, North Bengal Wild Animals Park, 5<sup>th</sup> Mile, Sevoke Road, Salugara, Siliguri-734008 (W.B), so that it reaches to the undersigned on or before **24 / 07 /2024** upto 3.00 p.m. and will be opened on the same day at 4.00 p.m. in presence of the quotationers. The undersigned is not bound to accept the lowest rate offered by the quotationers and may accept or reject any rate without assigning any reason.

Sl. No	Description of Item/Works	Quantity	Estimate Rate @ (Rs.)	Estimate Value
1	Taking out carefully G.C.I. or C.I. or asbestos sheets (including ridges etc.) from roof or wall after unscrewing bolts, nuts, screws etc. and stacking the material at site as directed.	27.00 M2	41.00/M2	1107.00
2	Cutting to requisite length or shape departmental R.S. joists, channels, angles, tees, plates etc.	139.60 CM2	8.00/CM2	1116.80
3	M.S. structural works in columns, beams etc. with simple rolled structural members (e.g. joists, angle, channel sections conforming to IS: 226, IS: 808 & SP (6)- 1964 connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in charge complete etc. i) For structural members of specified sections weighing less than 22.5 Kg./m	0.167 M.T	74571.00/M.T	12453.36
4	M.S. structural works with hollow sections (square or rectangular shape) conforming to IS: 806-1968 & IS:1161-1998) connected to one another with bracket, gusset, cleat as per design, drawing & direction of Engineer-in-Charge complete including cutting to requisite shape & size, fabrication including metal arc welding conforming to IS: 816-1969 & IS: 9595 using electrodes of approved make and brand conforming to IS:814- 2004, haulage, hoisting and erection all complete. i) For roof truss works a) Span up to 12 Mtr.	0.7 M.T	74284.00/M.T	51998.80
5	Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	46.74 M2	29.00/M2	1355.46

6	Painting with best quality synthetic enamel paint of approved make and brand etc. I) Two Coat.	46.74 M2	72.00/M2	3365.28
			<b>Sub- Total-</b>	<b>71,396.70</b>
			<b>Add GST @ 18%</b>	<b>12,851.41</b>
				<b>84,248.10</b>
			<b>Add CESS @1%</b>	<b>842.48</b>
			<b>Grand Total-</b>	<b>85,090.59</b>
			<b>or Say</b>	<b>85,091.00</b>



Director

North Bengal Wild Animals Park

Dated: - 15/07/2024

**Memo No. 615 /Q-28(MISC)/NBWAP/2024-25**

Copy forwarded for information and taking necessary action to:-

1. The Member Secretary, WBZA
2. The Asst. Director, NBWAP
3. Veterinary Officer, NBWAP
4. Range Officer, NBWAP
5. Sub Assistant Engineer, NBWAP
6. Office Notice Board
7. Office Notice Board of SDO, Siliguri/BDO Rajganj Block/GP Dabgram-I, Salugara.



Director

North Bengal Wild Animals Park